



PRODUCT SUBMITTAL

TRI - HARD TOP

Surface hardening compound for fresh concrete floors



TRI- HARD TOP

Non-metallic cementitious floor hardener

Description

TRI- HARD TOP is a surface hardening compound is a quality controlled, factory Blended powder which is ready to use on site. It consists of hard wearing aggregates selected for their physical properties of abrasion and wear Resistance, Portland cement and special additives to improve workability.

This combination produces a material which is easy to trowel in the surface of fresh, wet concrete.

TRI- HARD TOP cures monolithically to provide a dense nonporous surface which is extremely hard wearing and abrasion resistant.

TRI- HARD TOP is available in natural (concrete Grey) color as standard. special Colors, including Brick Red, Green .



Standard compliance

The product is certified by (National Research Centre)

- ASTM (C579)
- ASTM (D4060)
- ASTM (C413)

Design criteria

The base concrete should have a minimum cement content of 300 Kg/m³. The concrete mix should be designed to minimize segregation and control bleeding , although some limited bleed is desirable to ensure sufficient moisture is available to wet out **TRI- HARD TOP** when it is first applied. the use of water reducing admixtures from **Tri-Mix** range is strongly recommended in order to achieve water/cement ratio below 0.55.

Uses

TRI- HARD TOP provides a highly abrasion resistance surface to fresh concrete floors by the dry shake method which ensure that hard wearing surface bonds monolithically to the base concrete . It is ideally suited for all industrial areas subjected to heavy traffic, e.g. power stations, agricultural buildings, distillation plants , laboratories , warehouse floors , work shops and all production areas.

Advantages

- Supplied ready to use - no additive required.
- Provides a hard abrasion resistant surface.
- Forms monolithic bond with fresh concrete.
- Hard, dense surface resistant to oil and grease.
- Available in range of colors to improve working environment.
- Non metallic aggregates - will not rust when wet.

Technical Data @°25c

Appearance	Concrete color (Grey)- Brick Red - Green.
Base	Cement , additives and special aggregates
Abrasion resistance ASTM D4060	179.3 mg loss in weight
Abrasion resistance for concrete surface	Approx. 316 %

Directions for use

TRI- HARD TOP should be applied at even application rate of 3 - 5 Kg/ m². It is recommended that the floor be marked off into bays of known area.

Sufficient materials should then be laid out to meet the recommended spread rate.

Application of Tri-Hard Top should begin without delay when the base concrete has stiffened to the point light foot traffic leaves an imprint. Any bleed water should now have evaporated, but the concrete should have a wet sheen.

In large floors it will be necessary to work progressively behind the laying team to ensure application at the correct time.

TRI- HARD TOP is applied in two stages:-

(1) The first application is broad cast at an even rate of 3 Kg/ m² onto the concrete surface.

When the material becomes uniformly dark by the absorption of moisture from the base concrete, this first application can be floated .

Wooden floats, or on large areas, a power may be used.

It is important however, that the surface is not overworked.

(2) Immediately after floating, the remaining 2 Kg/ m² of **TRI- HARD TOP** are applied evenly over the surface at right angle to the first.

Again, when moisture has been absorbed the surface can be floated in the same way as before.

Final finishing of the floor using the plates of the power float can be carried out when the floor has stiffened sufficiently so that damage will not be caused.

any addition of water tower out the surface on either the first or second application of Tri-Hard Top will be detrimental to the overall quality of the floor.

Curing

Proper curing of concrete floors treated with **TRI- HARD TOP** is essential to the physical properties of the finished floor.

The most effective method of curing is to use **Tri-Cure** which should be applied on the finished floor 10 minutes after the power floating operation has been completed.

Coverage

3 Kg/m² for light traffic

5 Kg/m² for medium traffic to heavy traffic.

Package

TRI- HARD TOP is available in packing Sack 25 kg .

Shelf Life

12 months in unopened condition if stored as Per the recommendations.

Exposure to high temperature and humidity will result in considerable deterioration of the product and reduce its shelf life.

Storage conditions

- Store the material in a cool, dry and covered place.
- Temperature should not exceed 35 °C.
- Do not expose the pails to direct sunlight and keep away from all sources of heat.

Health and safety responsibility

- Workplace health and safety is all about sensibly managing risks to protect TRI-CHEM's workers and business.
- ISO 45001 is a systematic health and safety management is characterized by strong leadership involving managers, workers, suppliers, contractors and customers and also health and safety management is an essential part of the movement towards sustainable development.
- Spillages should be washed down immediately.
- PPE in accordance with the health and safety rules should be used during the materials application.
- For irritant effects of the non-cured material, avoid contact with skin and eyes during storage and application.

Sustainability and environmental accountability

- TRI-CHEM's Environmental sustainability is the accountability to conserve natural resources and protect global ecosystems to support health and well-being for this a more positive approach is that accountability guides the actions of power-holders towards more socially and environmentally sustainable results.

Technical support

- For any technical support, please contact TRI-CHEM technical office or representatives.

Institutional Excellence and quality performance

- Institutional excellence in TRI-CHEM refers to achieving high levels of performance, quality and effectiveness in all aspects of TRI-CHEM company's work, it involves a systematic and continuous effort to improve an organization's performance by applying best practices, innovative approaches and evidence-based strategies, institutional excellence spans various areas, such as training, research, innovation, community engagement, governance, management and sustainability, and involves setting high standards, measuring performance against these standards and continuously improving performance to meet or exceed these standards, excellence in TRI-CHEM also includes a culture of continuous improvement and learning, where everyone in the organization is committed to achieving the organization's goals, working together to find solutions to challenges and opportunities, and requires a collaborative approach that includes all stakeholders.

- All products originating from TRI-CHEM facility are manufactured under a quality management system independently certified to conform the requirements of the quality standards (ISO 9001:2015).

Disclaimer

- While TRI-CHEM guarantees its products against defective materials, the use and application of these products are made without guarantee since the conditions of their application are beyond its control.
- TRI-CHEM is recommended to verify with TRI-CHEM that the product is suitable for the intended use, and that this data sheet version is the latest one.
- TRI-CHEM may modify it without prior notice and technical characteristics are listed for guidance only.
- Any specification, recommendation or information mentioned in this product data sheet is (to TRI-CHEM's best knowledge) true and reliable.

- However, because TRI-CHEM has no influence on the application method of these products and the care taken, the company cannot accept any liability arising from the use of its products.

TRI-CHEM's warranty is therefore limited to the quality of the materials supplied which are guaranteed against defective materials.



Factory & Head Office:

6 October City - 4th Industrial Zone - Al Oula Industrial Zone Plot No.: 14
Tel.: (002) 011 195 48267 - Sales: (002) 010 007 88817 - (002) 011 184 87597
Technical Support Call : (002) 011 184 87880 - Email: sales@trichem-eg.com
www.trichem-eg.com



PRODUCT SUBMITTAL

TRI - HARD TOP

Surface hardening compound for fresh concrete floors

NRCR
2 National research
center report





Test Report

Report No.

Client

Authority & date

Items Tested

Results

Report Typist

Test carried by

Authorized by

Issue date

**Condition of Test
& Issue**

MO1 6215 12 2025

Tri-chem Construction chemicals

Request Orders 10/12/2024

Tri- Hard top

The detailed test results are given on the following pages of this report (4 pages) .

* **Mis. Naglaa Mohamed-Sara Abdel Reheam**
Noha Samir

* **Mis . Fatma El Zahraa Fikry**

* **H.Eng. Ahmed Said**

* **Chem. Amr El Shafey**

* **Dr. Abou El Ftouh Abd El Hakem**

Prof. Dr. Mostafa Zaki Mostafa

* **The Supervisor of ceramics, Polymer and Solid Matter Department.**

* **Management Representative and Quality Assurance Manager.**

19/1/2025

The test speciemen was conditioned at 23 °C with a humidity of 60 % and the needed calibrations as well as balancing of the all used machines were always done .





NATIONAL RESEARCH CENTRE
TAHRIR St. DOKKI, CAIRO, EGYPT
Central Unit For Analysis And
Scientific Services (CUASS)
Material Test Lab.

المركز القومي للبحوث
الدقي . القاهرة . جمهورية مصر العربية
وحدة التحاليل و الخدمات العلمية المركزية
معمل اختبار المواد



To / Tri-chem Construction chemicals

Dear Sir.,

With correspondence to your request dated 10/12/2024 concerning the testing sample of Tri- Hard top , We would like to inform you that the all following needed tests were carried out which namely:

- 1- Compressive strength test after 28days according to ASTM C579*
- 2- Abrasion Resistance Test according to ASTM D4060*
- 3- Water absorption test according to ASTM C413*

We would like to inform you that the needed test was carried out taking into consideration the following conditions :

- 1- In all mechanical properties GALDABINI – QUASAR 600 – Made In Italy Universal Testing Machine was used This type has a self calibration , zero adjusting and automatic balance , which are done daily before testing or during testing this testing instrument is accompanied by a highly reliable system for evaluating the mechanical properties .*
- 2-Measuring drum of sensitivity ± 0.01 mm was used for dimensions evaluation.*
- 3- On heating a Memmert West Germany oven was used .*
- 4- Weighing Balance with tolerance + 0.0001 g was used in determining the weights .*
- 5- In Abrasion resistance machine type Taber Dual Abraser.*
- 5- All used Machineries and apparatuses were calibrated periodically.*

The following tables give the obtained results representing the sample delivered from your company .





Test results on a sample of Tri- Hard top
Delivered from Tri-chem Construction chemicals

1- Compressive strength test after 28days

according to ASTM C579

No.	Compressive strength (N/mm2)	Mean (N/mm2)
1	53.93	55.35
2	57.01	
3	56.52	
4	54.11	
5	55.19	

2- Abrasion Resistance Test according to ASTM D4060

Cycle	Weight (g)	Wheal	Weight loss Control (mg)	Weight loss sample (mg)
1000	1000	CS17	373.1	118.6

3- Water absorption test according to ASTM C413

No	Water absorption (%)	The mean value (%)
1	8.93	9.26
2	9.81	
3	9.05	





NATIONAL RESEARCH CENTRE
TAHRIR St. DOKKI, CAIRO, EGYPT
Central Unit For Analysis And
Scientific Services (CUASS)
Material Test Lab.

المركز القومي للبحوث

الدقي . القاهرة . جمهورية مصر العربية
وحدة التحاليل والخدمات العلمية المركزية
معمل اختبار المواد



*This report was given to you representing only the results for the testing sample of Tri- Hard top , Delivered from Tri-chem Construction chemicals , These results and conclusions were given to you without any responsibility on **THE CERAMICS, POLYMERS AND SOLID MATTER DEP. of THE MATERIAL TEST LAB in THE NATIONAL RESEARCH CENTRE** for pick up the samples to be tested .*

**Head of Director of The Board of Central Department
for Scientific Analysis and Tests**

&

SUPERVISOR
**OF CERAMICS, POLYMER AND
SOLID MATTER DEPARTMENT**

PROF.DR. MOSTAFA ZAKI MOSTAFA




PRODUCT SUBMITTAL

TRI - HARD TOP

Surface hardening compound for fresh concrete floors

4 **APPROVALS**
Product
Certificates



Project: 10th of Ramadan Railway Project – Phase 3

Doc. Reference:	RedCncrt-3L02-CO-CER-QAQC-158-0034
Subject:	QAQC - 3L02 Nativity Cathedral Station - Prequalification of Tri-Chem (EPOXY COATING ANTI DUST - Construction Chemicals) Rev.1
WF Ref.:	016536
Date:	May 20, 2025

The Documents submitted by the contractor are revised against the following:

1. WF-000765: Detailed Design-Architecture Arrangement Specification for Phase 3 - Rev.2 which had been evaluated with code "B" on 30/10/2023.
2. **WF-000651: QAQC - 3L04 Octagon Station - Prequalification of Tri-Chem (Construction Chemicals) - Rev. 1 had been approved for civil works with code "C" on 17/10/2023.**
3. **Refer to previous approval for epoxy and polyurethane paintings of phase1,2 & 3.**

Comments:

1) Scope & Location	Scope: Epoxy Coating Anti Dust Location: as per approved design drawings
2) Company Profile:	Tri-Chem - Construction Chemicals is evaluated before "refer to WF-000651", the profile includes the following legal documents: ▪ Commercial register issued on 20/2/2011 and valid to 19/2/2026 with a starting capital of 510,000 EGP upgraded to 2M EGP. ▪ Industrial registration certificate issued from (IDA) on 24/1/2023 and valid to 23/1/2028. ▪ Company profile "pages 134- 156".
3) Product Technical Data Sheet:	The profile includes the following data sheets: ▪ Tri-Tile Grout "pages 6 – 8". ▪ Tri-Cure WP (Concrete curing compound) "pages 36 – 37". ▪ Tri-Latex SBR (Concrete Bonding Agent) "pages 65-67". ▪ Tri-Fix 444 (Ceramic Adhesive) "pages 95-98". ▪ Tri-Concrete Fiber (plaster, mortar & screed) "pages 106- 108". ▪ TRI-FIX UW (Tile & Ceramic adhesive for damp and under water conditions) "pages 583 – 584".

Project: 10th of Ramadan Railway Project – Phase 3

	▪ Tri - Grout AG (non-Shrinkage Cementitious Grouting Mortar) “pages 611 – 613”. ▪ TRI - HARD TOP (Surface hardening compound for fresh concrete floors) “pages 638 – 641”. ▪ TRI - Seal 307 (polymer cementitious coating) “pages 672 – 675”. ▪ TRI - ZINC P 11 Zinc (Epoxy and Anti-corrosion coating for Iron and steel) “pages 725 – 728”. ▪ Tri - Grout HF (non- shrink cementitious grout) “pages 750 – 752”. ▪ Solvent Free Epoxy System “pages 387 -494” as follows: a) Primer: TRI- PRIME 1010 b) Putty: TRI- POXY PUTTY 1050 c) Top Coat: TRI - FLOOR 1010 d) Epoxy Mortar: TRI- FIX F 330
4) Compliance Sheet:	Not included and shall be submitted with the material submittal (MAS)
5) Product Safety Data Sheet:	Not included and shall be submitted with the material submittal (MAS)
6) Method of Statement:	Not included and shall be submitted with the material submittal (MAS)
7) Qualification Certificates	The profile includes the following: ▪ Production Facility Certification Certificate issued from National organization for potable water & sanitary drainage for (20) products on 21/5/2021 “pages 18-19”. ▪ Recommendation letter issued from Clarity Engineering Center for using materials in fuel stations (No date). ▪ ISO 45001:2018 expired on 14/7/2024. ▪ ISO 9011:2015 expired on 11/7/2024. ▪ ISO14001:2015 expired on 13/7/2024.
8) Job References	Noted.
9) Quality Certificates	It includes test reports issued from NRC for the following materials:



Project: 10th of Ramadan Railway Project – Phase 3

	▪ Tri-Tile grout on 21/11/2021. ▪ Tri-Cure WP on 13/5/2019. ▪ Tri-Latex SBR on 10/8/2022. ▪ Tri-Fix 444 on 2/4/2019. ▪ Tri-Concrete Fiber on 17/1/2021. ▪ TRI- PRIME 1010 on 17/10/2019. ▪ TRI - FLOOR 1010 on 19/5/2022. ▪ TRI- FIX F 330 on 30/3/2021. ▪ TRI-FIX UW on 19/11/2023. ▪ Tri - Grout AG on 3/2/2021. ▪ TRI - HARD TOP on 3/2/2021. ▪ TRI - Seal 307 on 29/9/2024. ▪ TRI - ZINC P 11 Zinc on 6/11/2024. ▪ Tri - Grout HF. ▪ Other test reports issued from Master-lab (Dr. Ahmed Fathy Abdelaziz) on 1/10/2024.
10) Previous Approvals:	The profile includes approvals for Tri-Tile grout. from: ▪ Systra for Wadi El Natroun Regional Station [construction Chemicals] (Electric Express Train), Raafat Miller consulting, ECG, EHAF, Hydro and others “pages 5 - 32”. ▪ Other approvals for other materials (Ex. Concrete curing compound, Tri-Latex SBR). ▪ A long list of consultant’s approvals is included “227 pages from 157 – 384” but they are unreadable due to of poor resolution”. ▪ Epoxy system approvals from multiple consultants across various projects “pages 399 -
11) Sample:	▪ Submit samples for the system layers on hard boards with the material submittal (MAS). ▪ Colors as per NAT/Consultant selection.
12) Mockup:	Prepare a mockup onsite before supply to inspect the workmanship.
13) Shop drawings:	Submit the required shop drawings before supply.
<u>Conclusion</u>	

Project Engineer



Project Contractors



Employer



Project: 10th of Ramadan Railway Project – Phase 3

1. **Tri-Chem - Construction Chemicals prequalification is approved; however, the contractor must submit a Material Submittal (MAS) for each intended material, ensuring compliance with the project specifications and B.O.Q.**
2. The contractor shall fulfil the above and the following comments with the material submittal (MAS) for final approval of NAT.
3. **Submit also data sheet and samples for Treatment (10) Poly-urethane coating.**
4. The contractor is obligated to do all the required tests in an approved certified laboratory selected by NAT, witnessed by NAT/Consultant according to projects specification (refer to 20 Quality Control).

Approval Status:

Code "B" Approved with Comments.

Report prepared and reviewed by

Eng. Mohamed Al assal



MDA
DEVELOPMENTS



مشروع رافيل - شمال محور المشير طنطاوي - القاهرة
مشروع المبنى العام بجميع المستلزمات (مستلزمي 230 سرير)

طلب اعتماد مواد

المرجع : الهيئة الهندسية للقوات المسلحة

الاستشاري: (DIAA CONSULT) MDA DEVELOPMENTS

مقدم من : الصفا للمقاولات	موجه إلى: MDA / DIAA CONSULT
مدير المكتب الفني	مدير المشروع
تاريخ: 2024 / 1 / 1	اسم وتوقيع المستلم:
شركة الصفا للمقاولات العمومية	تاريخ: 2024 / 1 / 1

Rev.00

Document No.: Raville-ELSAFA-MDA/D-H230-MAT-040

م	عدد الترخيص	المرجع	الوصف	المنتج / المصنع	الملاحظات
1	3	تراي - هارد توب	Tri-Hard Top (Dry Shake Hardner)	تراي - هيم للمقاولات البناء	1- متابعة أعمال 2- الاختبارات 3- المعاينة

تعهد المقاول: المستندات المرفقة تم تسليمها ومراجعتها من حيث تطابقها مع العقد وتعتبر مقبولة للاستخدام في هذا المشروع من قبل المقاول

الاستشاري المعتمد	الإمضاء بواسطة	التوقيع:	تاريخ: 2024 / 1 / 1
الملاحظات			
لا مانع من اعتماد المواد المرفقة "موقعاً لاختيار" المرفقة . على أن يتم تقديم عينات من المواد للاعتماد والمطابقة .			

(ع) = بعد التقديم بعد توافي الملاحظات

(أ) = معتمد

(د) = الطلب مرفوض وبعد التقديم مرة أخرى

(ب) = معتمد مع ملاحظات. يمكن للعمل أن يستمر بناءً على الملاحظات

اعتمد الاستشاري

تاريخ: 2024 / 1 / 1	الاسم: السيد / محمد	الاسم: السيد / محمد	التاريخ: 2024 / 1 / 1
تاريخ: 2024 / 1 / 1	الاسم: السيد / محمد	الاسم: السيد / محمد	التاريخ: 2024 / 1 / 1
21 SEP 2024		21 SEP 2024	
Site Received		Site Received	

MATERIAL SUBMITTAL (MS)

Project Name : Palm Hills - Alexandria Project No. : 1220 Employer : Palm Hills Site Supervision Consultant: EHAF		Package : CPD-CA-PHA-121-6-2024 Phase : Phase 2 Contractor : UECC																					
From : UECC To : EHAF Attn. : Eng. Kareem Soliman Subject : TRI-HARD TOP :- Concrete Surface Hardner		Date : 19-11-2024 Submittal Ref.: PHAP-1220-UECC-MS-AR-0456 UECC Ref. : UECC-EHF-0501-CBCS-MS-AR-0456																					
Material / Equipment For Approval: Description: Concrete Surface Hardner Specification Reference : ----- Quantity : 1 Bill of Quantities Reference : ----- Attachments: Sample & Data Sheet																							
Manufacturer's Details : Attached Manufacturer : Tri-Chem. Model Number : ----- Serial number : ----- Date of arrival on site: ----- Country of Origin: Egypt Certificate of origin: ----- Bill of lading : ----- Storage Location: -----																							
Action Code Legend: (A) Approved (B) Approved as Noted (C) Revise and Resubmit (D) Rejected Notes : ▪ Production, supply and /or implementation shall proceed only when action code is A / or B. ▪ Regarding action code C, resubmittal shall be within the limit set in the contract. ▪ Review does not relieve the contractor from responsibility of compliance with all requirements of contract documents. ▪ If rejected please see comments.																							
Consultant Comments: <table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Inspection Report:</th> <th style="text-align: center;">Yes/No</th> <th style="text-align: center;">Initials Inspector</th> <th style="text-align: center;">Engineer</th> </tr> </thead> <tbody> <tr> <td>1- Physical damage?</td> <td style="text-align: center;">N.O</td> <td style="text-align: center;">-----</td> <td style="text-align: center;">-----</td> </tr> <tr> <td>2- Details given above correct?</td> <td style="text-align: center;">Yes</td> <td style="text-align: center;">-----</td> <td style="text-align: center;">-----</td> </tr> <tr> <td>3- Conforms to approved submission?</td> <td style="text-align: center;">Yes</td> <td style="text-align: center;">-----</td> <td style="text-align: center;">-----</td> </tr> <tr> <td>4- Accessories / Spare parts included?</td> <td style="text-align: center;">N.O</td> <td style="text-align: center;">-----</td> <td style="text-align: center;">-----</td> </tr> </tbody> </table> Remarks : Sample attached.				Inspection Report:	Yes/No	Initials Inspector	Engineer	1- Physical damage?	N.O	-----	-----	2- Details given above correct?	Yes	-----	-----	3- Conforms to approved submission?	Yes	-----	-----	4- Accessories / Spare parts included?	N.O	-----	-----
Inspection Report:	Yes/No	Initials Inspector	Engineer																				
1- Physical damage?	N.O	-----	-----																				
2- Details given above correct?	Yes	-----	-----																				
3- Conforms to approved submission?	Yes	-----	-----																				
4- Accessories / Spare parts included?	N.O	-----	-----																				
Consultant Manager Remarks: approved as per attached documents and approvals as a second choice final																							
Actions required from Contractor : approval after applying sample on site, follow manufacturer' instructions																							
Attachments: ----- ☐ Hard Copy ☐ Soft Copy (CD) Site Supervision Consultant Authorized Representative																							
Employer's Representative Comments (if required) : Employer Authorized Representative																							



SHAKER
CONSULTANCY GROUP



KASED KHAIR
GENERAL SUPPLIES AND CONTRACTING

Project: East Alexandria Development

Project Operation: General

Area : Army Force Land

Location:

Page 1 of 1

From: KASED KHAIR for General Supplies and Contracting

To: Shaker Consultancy Group

Material Submittal (MS)

Action

MS Ref. No.

EAD-GEN-KAS-SCG-ARCH-MS-0004

A: Approved

Rev:

00

B: Approved as noted

Date:

7/10/2024

C: Not Approved

Discipline

ARCH

D: Not Required

Attachment

Submittal for "TRI-CHEM" (35 Pages)

DCR : Document Control

Sent

by

Contractor KASED KHAIR for General Supplies and Contracting:

Signature:

Date:

07 OCT 2024

Time:

Received

by SCG

Signature:

Date:

Time:

2024 -10- 08

تطوير شرق الاسكندرية

SCG

REFERENCE STANDARDS, CERTIFICATES, QUALITY ASSURANCES, PERFORMANCE REQUIREMENTS

S.N.	Type	Description
1	TRI-Hard Top "TRI-CHEM"	Surface Hardening Compound For Fresh Concrete Floors

Consultant's Remarks:

لا مانع من اعتماد المادة المقترحة (TRI-Hard Top) للحصول على سطح اسس كه ادق والذو
الدرجات التي انقذت من المقاومة للبرق والتآكل لجميع الدرجات المعروفة للاعمال
المذكورة اعلاه.

يرافى المتاول توضيح لماكم استخدام مادة TRI-Hard Top (لمعرفة شطب السطح النهائي)

Consultant's Representative:
Signature & Date

Ibrahim Elshonbagy.
7-12-2024.

Document Control Representative
Signature & Date

09 DEC 2024

Received

Received by Consultant
Signature & Date



KASED KHAIR
FOR GENERAL SUPPLIES & CONTRACTING

08 DEC 2024

East Alex Development

يتم المتاول بعمل عينه مرقعة وعرضها على الاستشاري وطام الاسراف لاتخاذها ، ولا يتم التوريد الا
بعد اعتماد العينة وتلافى ، صج الا - الا - الا

Main Contractor		Consultant		Sub-Contractor	
					
Material SUBMITTAL				Ref.: NDH-C-MSF-0013	Date: 21/Jun/24
Subject: HARDENER				Discipline: ☒ Elec ☐ Mech ☐ Arch	Spec Ref: NDH PS7
Project Name: NDH PS7 220/66/11 KV Substation				Site Name: 220/66/11 KV Substation	
From: Arcon Group	Name: mohamed Ismail	Signature: 		Spec Ref:	
To: Elsewedy Electric T&D	Name:	Signature: 			
Attachment:				Total No. of Pages:	Dwg No.
Distribution: Project Manager ☒ Construction Project Manager ☒ Project Coordinator ☐ Quality Control ☒ Others (Specify) ☐ Others (Specify) ☐					
Material Description: Tri Hard Top (Tri-Chem) Spec Code: BOQ Code: Date Received: Date Returned: Drawing No. Submittal No. NDH-C-MSF-0013 Manufacturer Supplier/Agent Name: Name: Phone: Phone:					
Information submitted and attached: Certificates ☐ Shop Drawings ☐ As Built Drawings ☐ Technical Brochure ☐ Samples ☐ Warranty ☐ Specifications ☐ Catalogues and Manuals ☐ Others (Specify) ☐					
Contractor's Comments:					
Name:		Signature:		Date:	
Consultant/Owner Comments:					
See Attachment ☐					
Status: Approved A ☐ Revise and submit C ☐ Approved as not B ☒ Reject D ☐ Name: Signature: Date:					
Project Manger /Site Manager Signature: Date:					



٧٦٢٦
٩٠٩٦/٨/٩٧

الهيئة الهندسية للقوات المسلحة
إدارة المشروعات الكبرى
فرع التصميمات الإنشائية
التقيد: إنش/ مشروعات/ ٢٠٢٤
التاريخ: ٢٧/٠٨/٢٠٢٤

عدد المرفقات: (١)
الموضوع: بشأن المسطر بعد

إلى / مكتب السيد معاهد المدير للإنتاج والتنفيذ قطاع تنفيذ مشروعات رقم "١٦"

إيماءاً إلى مشروع تجمع (مستنى - تجارى-إدارى) (MIDWAY) تطوير أرض مركز تدريب
السائقين سابقاً وبالإشارة إلى كتابكم رقم (٣٠٦٦) بتاريخ ٢٠٢٤/٠٧/٣٠ بشأن أعمال مادة
(Hard Top) الخاص ببلاطات الهليكوبتر (SOG) بالمشروع.

يرجى التكرم الإحاطة بالآتى:

١- تم مراجعة المواصفات الفنية لمادة (Hard Top) الخاصة بالارضيات الخرسانية إنتاج شركة (تراي
- كيم) لمواد البناء المطلوب استخدامها بالمشروع والمرفقة بكتابكم المشار إليه بعاليه.

٢- لا مانع من وجهة النظر الإنشائية من استخدام مادة (Hard Top) الخاصة بالارضيات الخرسانية طبقاً
للإستخدامات الموضحة بالمواصفات الفنية للمادة المقدمة من الشركة على أن يتم تنفيذ عينة بواسطة
الشركات المنفذة تحت إشراف إستشارى مراقبة الجودة بالمشروع والمكتب الإستشارى المشرف على
المشروع واختبارها ومراجعة سعر بند تنفيذ الأرضيات بتنشيطيتها طبقاً لما هو وارد بمقايضة الأعمال
الأصلية للمشروع.

٣- التنبيه على الشركات المنفذة بالمشروع بالإنترام بمعدلات الإستخدام لمادة (Hard Top) الخاصة
بالارضيات الخرسانية المستخدمة طبقاً لما هو وارد بالمواصفات الفنية للشركة المنتجة للمواد وطبقاً
لتوصيات المكتب الإستشارى لضبط الجودة بالمشروع وتحت إشراف المكتب الإستشارى المشرف
على المشروع.

٤- مرفق طيه صورة من موافقة شركة العزل (تراي - كيم) على شروط التعاقد والعمل مع إدارة
المشروعات الكبرى.

مع وافر التحية ...

التوقيع (٢٨٢٧٢٧)
عميد / محمد حسان أحمد
مساعد المدير للمشروعات

التوقيع (٢٨٢٧٢٧)
راند / محمد سعد زغلول
رئيس فرع التصميمات الإنشائية

سما محمد المدير للمشروعات
التقيد: ١٦٦٢
التاريخ: ٨/٩٧/٢٠٢٤

Material Submittal

Project Data

Project Title	New Delta 08 - 220/66/22KV SUBSTATION	Project NO. P199
Project Owner	Egyptian Electrical Transmission Company (EETC)	
Project Main Contractor	MADKOUR PROJECTS	
Project Sub Contractor	ARCON	

Document Data

Document Name	Tri Hard Top Grey	Document Code P199-ARCON-MDK-MS-CIVIL-0015
Document Date	Document Type	Document Pages
12/6/2024	A4	
		Department Res. ☒ Technical Office ☐ Quality Control


Document Revisions

Revision	Revision Date	Revision Status	Create By		
Rev.0		For approval	Hamza Fares		

Document Type

Submitted for:	☒ Approval	☐ Information	☐ Other
Submittal type:	☐ Technical Submittal	☒ Material Submittal	☐ As Built
	☐ Q.S	☐ Shop Drawing	☐ Invoices
			☐ Others

Review Status

Name:	Hamza Fares
Signature:	

Approval Status

Notes:	Code (B) المطابق بعد التوريد بالبحر ر. الناصر
Status	☐ Approved ☒ Approved with comments ☐ Rejected ☐ For information
Signature:	

Flex ASEPTO Liquid Packaging Plant Project

consultant



client

FLEX ASEPTO (EGYPT) S.A.E.



Main contractor



CIVIL

MS (Material Submittal)

MS-CV

021

Rev.

00

Date

14/Aug/2024

Time

Item Name

HARD TOP - SEALENT - POLYPORPLIN

Attachement

P.P

BOQ Ref.

Supplier

TRY CHEN

Description :

HARD TOP - SEALENT - CONCRETE FIBER POLYPORPLIN

Contractor

Q.C Engineer



Project Manager

Responsible Receival

Receive Date & Time

Received Stamp

Date 14/Aug/2024

Time

Consultant Reply

Approve (A)

Approve as noted (B)

Revise and Resubmit (C)

Rejected (D)

1. Ensure Material is used as specified in the BOQ and manufacturer's documentation.
2. Store materials in dry covered area on Pallets, following manufacturer's guidelines.

Consultant

Technical Office

Responsible Engineer

Project Manager

MS-CV 021

Rev 00

Page1/1



LARSEN & TOUBRO CONSTRUCTION

Project:

Project Quality Plan

WP GEN 02 F05 R0

Page 1 of 2

CONTRACTOR : L&T CO.

DATE 11-06-2019 /05/2019

MAS NO : 32

REV NO.: 0

To:

EETC

Attention:

CONTRACT No:

PROJECT:

S4 Ras - Ghareb 500/220/22KV GIS S/s

MATERIAL APPROVAL SUBMITAL (MAS)

T-Spec Ref.	Rev.	Description of Material	Model No/Part No	Source/ Country of Manufacturing
	0	Novo Hard floor for hard top for floor	Novo hard top	Novochem CO.
✓	0	Tri-Hard top for hard top for floor	Tri-Hard top	Chem CO.
	0	Kem floor HF ,hard top for floor	Kem floor HF	Prokem CO.

Location of Usage:

ALL BUILDINGS & Roads.

Material Used for:

Hard floor.

Supplier

Attachments:

☐ catalog ☐ Data sheet

On Behalf of Contractor

Name: Amr ElShahawy

Position:QA/QC

Sign:

Date:

11/5/2019

Comments :

ممتازة

11-6-2019

Hand


Material Approval Request


Date / تاريخ : 20-10-2018						Project Name / اسم المشروع : 25 Years Anniversary Celebrations 2018					
Type of work / نوع العمل :						Contractor / المقاول :					
Sheet / ورقة :		Page / صفحة :		Job No. / رقم العمل :		Estimate / تقدير :		Contract Value / قيمة العقد :		Remarks / ملاحظات :	
Request Number / رقم الطلب :						Material Name / اسم المادة :					
CNC02-CRC-UDC-MAR-0118						24-10-19					
Receiver Name / اسم المستلم :						Responsible Material / مسئول المادة :					
Tri-Chem						نتراي - هارد توب					
Address / عنوان :											
Signature / توقيع :						Name / اسم :					
Section Manager / مدير القسم :						Section Engineer / مهندس القسم :					
Evaluation / التقييم :						Date Received / التاريخ المستلم :					
Requested / المطلوب :		Approved / الموافق :		Inspected / المفتش :		Accepted / المقبول :		Rejected / المرفوض :		Remarks / ملاحظات :	
Inspection Result / نتيجة الفحص :											

لما منع من اعتماد المنتج فسيأطبقاً للاختبارات المرفقة
لما أن يتم تقديم عينات من المنتج للاعتماد والمطابقة

RECEIVED
28 OCT 1958
CRC

MATERIAL SUBMITTAL SHEET (MS)

Contract Ref: (2924)		FME-BCF-Civil-S.O.G- MS -00025		Rev.0
To: ECG		Cc: BENYA CABLE	Discipline	
Contractor Signature: FME 		Submittal Issue Date 7/2/2022	Response Requested By FME	
Material Description/Location Project: BENYA CABLES FACTORY Location: EIN EL-SOKHNA, EGYPT Subject: TRI-HARD TOP (Surface hardening compound for fresh concrete floors)			Enclosure ☐ Drawing ☐ Literature ☐ Calculation ☒ Specification ☐ CD ☐ Other ☐ Sample	
Contract Specification Clause Ref: Divisions 03 Concrete SECTION 033000			 Benya Factory Project	
Manufacture:	Tri-chem			
Notice of Cost Variation		Reason for Alternatives:		
COMMENTS: لا يوجد أي ملاحظات على التصميم المقدم والجوهرية في التصميم المقدم				
Consultant / Engineer's Representative  Returned To Contractor: Document Status (A): Approved Consultants Group S.A. Benya Cable Factory-Al Sokhna Industrial Area (B): Revise and work may proceed subject to incorporation of changes indicated -Resubmit A: APPROVED NO WORK MAY PROCEED				
Date Received		(C): Rejected. Revise and Resubmit Work cannot proceed		
Signature		(D): For Information Only-Review not required		
Distribution:		IMPORTANT: This approval does not constitute acceptance of design details calculations analyses test methods or materials developed or selected by the contractor / supplier and does not relieve contractor / supplier from full compliance with contractual obligations.		
Contractor:		CONSULTANT / ENGINEER'S REPRESENTATIVE		
Cc: ECRD		Signature  Date 23-2-2022		



 23-2-2022



Sphinx Contracting Co.
شركة سفنكس للمقاولات

ELSEWEDY
ELECTRIC
T & D



SUBMITTAL

10-Jul-21

SCC-SDC-MAS-C-012-00

Subject:

TRI-HARD TOP

Discipline: ☒ Civil ☐ Arch

Project Name:

AL EMTDAD OF EL SADAT CITY
220/22/22 KV AIS SUBSTATION

☐ Elec ☐ Mech ☐ HVAC

From: SCC

Name: Ahmed Fouad

Signature:

Spec Ref:

To: EET&D

Name: Essam Rizk

Signature:

Attachment: Datasheet

Total No. of Pages: Dwg No.

Distribution:

Project Manager ☐ Construction Project Manager ☒ Project Coordinator ☐
Quality Control ☒ Others (Specify) ☐ Others (Specify) ☐

Material Description:

Concrete surface hardener

Spec Code:

BOQ Code:

Date Received:

Date Returned:

Drawing No.

Submittal No.

Manufacturer TRI-CHEM

Supplier/Agent

Phone:

E-mail:

Phone:

Phone:

Information submitted and attached:

Certificates ☒ Shop Drawings ☐ As Built Drawings ☐
Technical Brochure ☒ Samples ☐ Warranty ☐
Specifications ☐ Catalogues and Manuals ☒ Others (Data Sheet) ☐

Contract's Comments:

Name :

Signature:

Date:

Consultant/Owner Comments

See Attachment ☐

Status:

Approved A ☒ Revise and submit
Approved as note B ☐ Reject

C ☐
D ☐

Name :

Signature:

Date:

Project Manger /Site Manager

Signature:

Date:

SUBMITTAL FOR APPROVAL OF MATERIALS

التقديم للموافقة على المواد واعتماد المورد

Owner : JUSHI EGYPT

Construction Supervision Consultant : BENAA CONSULTING GROUP

Contractor : Reiada For Construction and Development

We request the Owner Representative's approval on the following Materials

مطلب موافقة ممثل المالك على المواد التالية

Project	المشروع	Kaolin project	Submittal No	25	رقم التقديم
Contract No.	رقم العقد		Title		العنوان
Zone	المنطقة	كاولين بروجكت	Rev. No	0	رقم المراجعة
Discipline	القسم	انشائي	Date	10/4/2022	No of Copies

SURFACE HARDENING COMPOUND IS A QUALITY CONTROLLED

وصف المواد

1-

مجال التطبيق

1- MATERIAL DESCRIPTION:

Area of Application TRI - HARD TOP رقم البند 2-6 انشائي

Drawings Ref مرجع الرسومات
Specification مواصفات
Enclosures المرفقات
BOQ Ref No :
Standards المعيار
Document No رقم الملف

Attach all relevant technical literature marked to identify relevant description, current test certificates, samples as appropriate

ملاحظة أرفق جميع الملفات ذات الصلة التقنية اللازمة لتحديد وصف ذات الصلة وشهادات الاختبار الحالي و العينات حسب الاقتضاء

2- MANUFACTURER / SUPPLIER TRI - CHEM

جهة التصنيع

الامتكانية

الوكيل المحلي

Company Name TRI - CHEM اسم الشركة
Address العنوان
Local Agent
Country of Origin EGYPT
Availability

3- DELIVERY STATUS

3- حالة التسليم : اعتماد مورد

Manufacturing Duration مدة التصنيع
Estimated Date of Arrival on site تاريخ التسليم في الموقع
Date Material Required on Site تاريخ المواد المطلوبه في الموقع
Delivery Duration
Latest Date for order

We certify that the above submitted items have been reviewed in detail and are correct and in strict conformity with the contract drawings and specifications except as otherwise stated and also that the material sources indicated above have been reviewed in detail and that they will supply the submitted items in full

تسليم بانه تم استعراض البنود المذكورة اعلاه المقدمة بالتفاصيل الصحيحة ومتفقة تماما مع الرسومات الموجوده في العقد باستثناء ما ينص على خلاف ذلك ، وايضا ان مصادر المواد المشار اليها اعلاه قد بالتفاصيل تم استعراضها بالتفصيل وانها ستوفر العناصر المقدمة بما يتفق تماما مع التسليم في الوقت المناسب

FOR THE CONTRACTOR

Technical Manager: Doc. Control Manager: مدير توثيق الملفات
QA/QC Manager: Project Manager: مدير المشروع

CONSULTANT'S COMMENTS :

لا مانع من الاعتماد على المورد طالما ان المواد المشار اليها اعلاه قد بالتفاصيل تم استعراضها بالتفصيل وانها ستوفر العناصر المقدمة بما يتفق تماما مع التسليم في الوقت المناسب

CONFORMS WITH DESIGN DRAWINGS
A ☐ APPROVED
B ☒ APPROVED AS NOTED
C ☐ REVISE AND RESUBMIT IS REQUIRED
D ☐ REJECTED

ACTION CODE
A Approved As Submitted
B Approved Except As Noted
C Revise and Resubmit
D Disapproved - Resubmitted
E Receipt Acknowledged

TO: THE CONTRACTOR

Approval shall not relieve the Contractor of its obligations and liabilities under the contract or constitute authorization of any change to Contract Documents, and therefore, shall not imply any recognition whatsoever of additional time or cost to the contract.

الموافقة لا تعفي المقاول من التزاماته بموجب العقد أو إذن من الاستشاري أي تغيير في وثائق العقد وبالتالي لا ينطوي على أي اعتراف من أي نوع من الوقت الإضافي أو تكلفة على العقد

For consultant: Name: Signature: Date: 2/1/2022
الاستشاري الاسم التوقيع التاريخ

FOR : THE OWNER REPRESENTATIVE COMMENTS:

ملاحظات ممثل المالك



(Submittal - MAT)

طلب اعتماد مواد

إلى الإستشاري :-	جماعة المهندسين الإستشاريين	من المقاول العام :	شركة ريدكون للتعمير
	ECG		

رقم الطلب	RD-ECG-MAT-ARCH-0186	الإصدار	1	التاريخ	25/07/2022
الموضوع	Tri - Hard Top (Dry shake Hardner)				
نوع الاعمال	إنشائي	معماري	كهرباء	ميكانيكا	مساحة
					أخرى

م	البيان / الوصف	عدد النسخ	عينة	المصنع / بلد الصنع	رمز المواصفات	رمز المقايضة
1	Tri - Hard Top (Dry shake Hardner)	3		Tri - CHEM		

المقاول	مهندس مكتب فني	مدير المكتب الفني
استلام الإستشاري	بواسطة:	بتاريخ:
		التوقيع:

ملاحظات الإستشاري

نظر إلى الملاحظات المرفقة (Page 4) .

By: [Signature] Date: [Blank]

Permission to proceed does not relieve the contractor from his contractual obligations.


الإستشاري المختص	الإعتماد بواسطة:	التوقيع:
------------------	------------------	----------

أ	معتمد	ج	يعاد التقديم مرة أخرى بعد اتمام الملاحظات
ب	معتمد مع ملاحظات - يمكن للمقاول ان يستمر ببناء على الملاحظات	د	الطلب مرفوض
	اعتماد الإستشاري	بتاريخ	25/7/2022
	استلام المقاول	بتاريخ	25/7/2022

التوزيع قبل الاعتماد :

المالك :	الإستشاري :
----------	-------------

التوزيع بعد الاعتماد :	المالك :
الإستشاري	مدني
معماري	كهرباء
تكييف	ميكانيكا
تخطيط	Q.S





Downtown Extention Project

Associated Consultant

المستشارون المتحدون

المستشارون المتحدون

المستشارون المتحدون



(Submittal - MAR)

طلب اعتماد مواد

إلى الإستشاري :-	المستشارون المتحدون	من المقاول العام :	اي اس جي سي للإتشاءات
	AC		ASGC Construction

رقم الطلب	ADTE-ASGC-AC-MAR-0467	الإصدار	5	التاريخ	5-Oct-2022
الموضوع	TRI-CHEM Surface hardener fresh concrete floors				
نوع الاعمال	إلشائي	معماري	كهرباء	ميكانيكا	مساحة
	☐	☒	☐	☐	☐

م	البيان / الوصف	عدد النسخ	المصنع / المقاول المنفذ	رمز المواصفات	رمز المقايمة	اعتماد الاستشاري
1	TRI-HARD TOP Surface hardener compound for fresh concrete floors	1	WACHEM	B-2-2-31 A-4-10		

05 OCT 2022

المقاول	مهندس مكتب فني مينا صبحي	مدير المكتب الفني م/ زومال سمير	مدير المشروع م/ محمد الرفاعي
استلام الإستشاري		التوقيع:	بتاريخ:

ASGC-Downtown_Al-Alamein

ملاحظات الإستشاري

الإستشاري المختص	الإعتماد بواسطة:	التوقيع:	بتاريخ:
------------------	------------------	----------	---------

يعاد التقديم مرة أخرى بعد اتمام الملاحظات

☐

ج

معمد

☐

1

الطلب مرفوض

☐

د

ب معتمد مع ملاحظات - يمكن للمقاول ان يستمر بناءا على الملاحظات

☐

ب

اعتماد الإستشاري	الاسم : م/	بتاريخ:
اعتماد المالك	الاسم : م/	بتاريخ:
ملاحظات المالك		
استلام المقاول :		
الاسم	التاريخ	

Associated Consultant	Approved
Code A	Approved With Comment
Code B	Revised & Resubmit
Code C	Rejected
Code D	For Your Information
FVI	

RECEIVED

06 OCT 2022

ASGC-Downtown_Al-Alamein

Received Stamp
١٧ أكتوبر ٢٠٢٢

تقرير تقديم مواد بالموقع
Material Submittal Report

Building Name: عمارات AUC & STRIP MALL		AUC & STRIP MALL إنشاء عمارات		: Name Project/مشروع اسم	
Owner/ المالك		NAB DESIGNS ENGINEERING		Consultant / الاستشاري	
Type of work/الاعمال نوع		ECONOMICAL & SAFE ENGINEERING		Consultant / الاستشاري	
Mechanical .Mech	Electrical .Elec	Finishing	Civil	Contractor / المقاول	
:Ref.no / الرقم المرجعي		: Date / تاريخ التقديم		Material / بيان المواد	
AUCB-ESE-SHK-MSR-CI-28		15/10/2022		TRI-HARD TOP	
00		:Rev.no / طبعة		: Name	

TRI-CHEM	:Supplier Name/اسم المورد	مادة تقسية للسطح الخرساني (هاردنر)	Description / وصف المواد Material
16 Page A4	: Attach/المرفقات		

Area of Application/التطبيق	لزوم أعمال المباني في المشروع
-----------------------------	-------------------------------

Name/الاسم : م / احمد حماد	مهندس الجودة
Signature/التوقيع	مدير المشروع
Review Result/نتيجة المراجعة	

Evaluation/التقييم		:Date Receive / تاريخ الاستلام	
D Rejected	C Rejected and resubmit	B Approved as noted	A Approved

الملاحظات / Notes :


اعتماد اطار ذلك بناءً على مراجعة الاستشاري



١- اتباع تعليمات المكتب الاستشاري

٢- اتباع الرضوخ للمكتب الاستشاري

٣- اتباع تعليمات الشركة المقاول

Consultant Project / استشاري المشروع	
Name/الاسم : م / احمد حماد	Quality Consultant استشاري الجودة
Signature/التوقيع	Contractor : استلام المقاول
Date/التاريخ : ١٦ / ١٠ / ٢٠٢٢	
Date/التاريخ :	

Project: Carrefour Damanhur Hyper Market	Client: Carrefour		 كارفور Carrefour		
	Consultant: Saleh & Hegab Architects -Engineers-Economic Studies		 صلاح هجاب Saleh & Hegab INTEGRATED ENGINEERING ECONOMIC STUDIES		
	Contractor: 2WIRES		 2 Wires General Contractor		
Material Submittal	Report No. 15	Date: 30-04-2023	Page 1/1		
Item	نراي - هارد توب	Location			
Drawing		Rev	00		
Submittals					
Ser.	Item Description	Discipline	Revision	Pages	Copies
1	مصعد لأسطح الأرضيات الخرسانية خليط جاهز للاستعمال مكون من أسمنت وإضافات وركام صلب مقاوم للتبري والاحتكاك المنتج حاصل على شهادة اختبار من المركز القومي للتبحوث.	نراي-كيم	00	1	2
Attached	Catalogue	Sample	☐		
	Data sheet	Drawings	☐		

Submitted by Technical Office:		Received By consultant:	
Title:	Architect Projects Manager & Procurement Engineer	Title:	
Name:	Walid Wagdy Hamid	Name:	
Signature:		Signature:	
Date:	30-04-2023	Date:	

Review and Approval:

Notes

001	Approved	☒
002	Approved as Noted	☐
003	Revise and Resubmit as Noted	☐
004	Rejected	☐

Received By consultant:

Two Wires
Sent
30 / 4 / 2023

Two Wires
Received
1 / 5 / 2023

Owner



Consultant



Contractor

Engineering
Consultant Union

Submittal No: نموذج رقم

Date: التاريخ: 2017/11/17

From The Contractor:

الشركة المصرية للبناء

من المقاول:

Signature: التوقيع

CONTRACTOR'S MATERIAL SUBMITTAL

طلب اعتماد عينات/مواد

New submittal : طلب جديد:	Re-submittal : إعادة تقديم:
MATERIAL DESCRIPTION وصف العينة / المواد (One item only this form) (هذا الطلب مخصص لبند واحد فقط)	AS SPECIFICATION [] مطابق للمواصفات ALTERNATIVE [] بند بديل
Drawing ref. رقم لوحة العقد:	BOQ Ref. No. رقم البند بالمقاييس:
Specification Ref. رقم مواصفة العقد:	standards, BS, DIN أكواد / مواصفات:
(attach all relevant technical literature marked to identify relevant descriptions, current test cert, sample etc.) مطلوب إرفاق كافة المستندات الفنية المؤكدة لمطابقة العينة / المواد لمتطلبات العقد	
MANUFACTURER / SUPPLIER Company Name : Tri - Chem - Hard- top خرسانة ممسوسة اسم المورد:	FOR CONSULTANT USE ONLY لاستخدام الاستشاري فقط
Address : العنوان: Local Agent : الوكيل المحلي:	APPROVED ☐ معتمدة
DELIVERY التوريد للموقع: Country of Origin : بلد المنشأ: Availability مدى توفره	APPROVED AS NOTED ☐ معتمدة بملاحظات
Manufacturer التصنيع Production Period مدة التصنيع Delivery Ex- Works مدة التجميع Total delivery time المدة الكلية للإنتاج Transport النقل Overland نقل برى وتشوين Sea Freight شحن بحرى Total Freight إجمالى مدد النقل	ADDITIONAL INFORMATION REQUIRED ☐ مطلوب معلومات إضافية
PROGRAMME البرنامج Date material required on site تاريخ احتياج المواد Estimated date of arrival on site التاريخ المتوقع للتوريد بالموقع	SAMPLE REQUIRED ☐ مطلوب عينة
ECU COMMENTS: تعليقات الاستشاري: المهندس المشرف Resident Engineer Comments of Employer's Representative & Project Director : تعليقات ممثل المالك ومدير المشروع:	TEST REQUIRED ☐ مطلوب إجراء اختبار
	MANUFACTURERES GUARANTEE REQUIRED ☐ مطلوب ضمان المصنع
	REVISE AND RESUBMIT ☐ تراجع وإعادة تقديمها
	NOT APPROVED ☐ مرفوضة

Al Jazi Project



MATERIAL SUBMITTAL FORM

Contract No.: PEG 1158

Package No.: CP04

TITLE: Helicopter Finished S.O.G For Roads (Tri-Chem).

SUBMITTAL NO.: 1158-CP04-CN-AL-MAR- 0127

TO: Hill International

DATE: 07-06-2023

FROM: Alecon

REVISION NO.:

Rev. 00

ATTN.: Eng. Walid Negm Senior (Project Directors) .

C/REF.:

MATERIAL SUBMISSION DESCRIPTION

Discipline: ARCH

Description of Material: Helicopter Finished S.O.G For Roads (TRI-Hard Top).

Manufacturer (Name & Address): Tri-Chem .

Supplier / Local Agent: Tri-Chem .

Specification: Section. 03330

BOQ Ref: 03330 Div. 03

Description of Attachments:

Description of Samples: No

Specification Comparison Sheet: Data Sheet

Comparison in case of Alternative Submittal:

CONTRACTOR SIGNATURE:

Date: 07-06-2023

PMC RECEIVED
Hill International

07 JUN 2023

Al Jazi Project
Received

CONSULTANT RECEIVE:

07 JUN 2023
rmc

RETURNED FROM CONSULTANT:

Al Jazi Project
Received

CONTRACTOR RECEIVE

RECEIVED

13 JUN 2023

ALECON

CONSTRUCTION SUPERVISION CONSULTANT'S COMMENTS

Name:

Signature:

Date:

PROJECT MANAGEMENT CONSULTANT'S REVIEW

Name:

Signature:

Date:

Employer's COMMENTS (optional)

Name:

Signature:

Date:

- Follows attached reply

Al Jazi Project



MATERIAL SUBMITTAL FORM

Contract No.: PEG 1158

Package No.: CP04

☐ A-APPROVED ☒ B-APPROVED AS NOTED, WORK MAY PROCEED - INCORPORATE COMMENTS ☐ C-REVISE / RESUBMIT ☐ D-REJECTED

CONSTRUCTION SUPERVISION CONSULTANT RESIDENT ENGINEER'S SIGNATURE

For & On behalf of (Consultant)

Name:

Signature:

Date:

- The submitted material is accepted as per project B.O.Q with the following notes:-
- 1) The Contractor must comply with manufacturer recommendation regarding handling storage and method of application
 - 2) Site mockup and method of statement is required before proceeding.
 - 3) the submitted material must achieve the performance required as specified in Project documents.
 - 4) The contractor must submit related shop drawing showing the area of application

[Signature]
11/06/2023

نموذج طلب اعتماد خامات (MS)

إسم المشروع: مشروع المجمع الطبي للأطفال بالمرحلة الثانية بأرض الفرع الدولي
جامعة القاهرة
مالك المشروع: جامعة القاهرة
الإشرافي العام: د. وليد عبدالمعتم - مكتب DAD
المقاول: الهيئة العربية للتصنيع
مدير المشروع للمقاول: م. هاني عامر

من: الهيئة العربية للتصنيع
التاريخ: 14/02/2023
إلى: د. وليد عبدالمعتم - مكتب Design & Development Consultants
الرقم المرجعي: MC-CU-DAD-ADP-MS-CIVIL-059
الإصدار: Rev 00
عناية السيد المهندس / خميس سيد أحمد.

خامة / معدة - الإتماد
الوصف: TRI - Hard Top (Surface Hardening Compound For Fresh Concrete Floor)
مرجع أرقام كميات الأعمال: الكمية:
مرجع المواصفات الفنية: مرجع المواصفات الفنية:

بيانات المصنع / المورد
المصنع / المورد: TRI - CHEM Construction Chemical
رقم الموديل:
مكان التخزين: موقع المشروع
المرفقات: Technical Data Sheet

بيانات لملا بواسطة إشرافي المشروع
من: د. وليد عبدالمعتم - مكتب DAD
إلى: الهيئة العربية للتصنيع.

حالة الإتماد:
☐ معتمد A ☒ معتمد بملاحظات ك ☐ معتمد بملاحظات C ☐ مرلوش D

ملاحظات:
- يتم التصديق / التوريد فقط في حالة (معتمد أو معتمد بملاحظات)
- في حالة (إعداد التقديم بعد تكميل الملاحظات) يتم إعادة التقديم بعد استيفاء الملاحظات
- في حالة (مرلوش) لا يتم تقديم نفس الخامة / المعدة مرة أخرى

الملاحظات:
تم منح تصديق التوريد خزانة مياه ومعدات لحد الأول، الثاني
مع المكتبين تين لتوريد

الاجراء المطلوب:

المرفقات:
إشرافي المشروع



Material Submittal Request

اسم المشروع :- كاري للصناعات الغذائية

نوع الأعمال / Type of work

ميكانيكا Mech.	كهرباء Elec.	تشطيبات Finishing	اقتصادي Civil
-------------------	-----------------	----------------------	------------------

اسم المقاول : ايه سي أو للمقاولات ACO - Construction

تاريخ التقديم :

31/7/2023

Hard top for S.O.G

اعتماد عينة مصد السطح لخرسانة الأرضيات
(غرف الامن و الكهرباء & غرفة المحولات و لوحات التوزيع)

نوع المستند

المقاول / Contractor

الاسم : م / عبد الرحمن عمر

مدير المكتب الفني

مدير المشروع

abd rahman

نتيجة المراجعة / Review Result

D	مرفوض Reject	C	يعاد التقديم Resubmit	B	معتمد بشروط Approved as noted	A	معتمد Approved
---	-----------------	---	--------------------------	---	----------------------------------	---	-------------------

#	Item	Description	Vendor name (brand)	Action code
1	HARD TOP FOR S.O.G	Surface hardening compound for fresh concrete floors.	TRI - HARD TOP TRI - CHEM for construction chemicals (Attached sample & data sheet)	B

: CONSULTANT NOTES

الموافق ٨/٨/٢٠٢٣ الموافق ٨/٨/٢٠٢٣ الموافق ٨/٨/٢٠٢٣
(50%) على أن يتم تسليم البورسلاند والمواد الموصلة
بالمسحوق (البيس) في المصير والخرابطة
ACO-Consultation

NAME: ENG / AHMED ABD EL HADY

DATE:

SIGNATURE:

٨/٨/٢٠٢٣



اسم المشروع: مشروع مدينة العلمين الجديدة مشروع ال 609 فدان قطار 3
شركة الإسكندرية للإنشاءات

Materials Submittal طلب اعتماد مواد

طلب جديد	رقم طلب الاعتماد:	ALM-finish - 176	رقم الطلب السابق:
طلب معاد تقديمه	تاريخ الطلب:	11-11-23	تاريخ الطلب السابق:
سبب تقديم طلب الاعتماد:	من أجل معلومات	☐	من أجل الملاحظات والتعليقات
الفرع:	من أجل الاعتماد	☐	من أجل الاعتماد
تطبيقات	معماري	☐	إشغلي
ميكانيكا	كهرباء	☐	أخرى
المرافق:	تطبيقات	☐	معماري
تطبيقات	ميكانيكا	☐	كهرباء
تطبيقات	ميكانيكا	☐	كهرباء

مستل	الاسم / الرقم / الوصف	البيد	المصدر	المصنع / المورد	مراجع المواصفات	المراجع القياسية	حالة الاعتماد
1	معالجة اسطح الخرسانة TRI CHEM			TRI CHEM			☒

ملاحظات المقاول:

استثناء:

مهندس الجودة (المقاول):

اسم المهندس / مهندس:

التوقيع:

التاريخ:

توصيات الاستشاري:

الموافقة على اعتماد المواد المقدمة أعلاه لا يفي بالمقاول من مسؤولياته حسب العقد.

Code-B وعليه لزاماً من لدينامية الاعتماد المبدي للمادة المقدمة به إلى كملومات تقنية فقط (Technical Data) لنوعية **TRI-Heavy Top** ومنت انتاج شركة (قراي - كيم - TRI-CHEM) وذلك وفقاً لبايلر حرج المادة المقدمة لمعالجة الأسطح للخرسانة (أسطح الخرسانة) المقدمة للاعتماد بوجه عام ولا مانع من ذلك ولكن بدون أضرار تكلفه بالية إضافة إلى المالك حيث أنها تستخدم لمعالجة عيوب في أصول الصناعة وليس تستخدم بنفسها في المشروع. لقد تم هذا الاعتماد وفقاً للعمل وبالميزانية المود المحدد لإنهاء المشروع. عليكم تقديم طريقة التنفيذ للمواد بحسب الاعتماد بحسب إبياع تعليمات المصنعة في أعمال التنفيذ بالموقع وكذلك أصول الصناعة وعمل عيب بالموقع. (Mock-up on site) والمساهمة قبل جاز الإشراف بالمركم. يتم أخذ عينات عشوائية من كل توريد وذلك بموجب تعليمات كافة الاختبارات المتعلقة بالمادة أو المراكز الحكومية المعتمدة بهذا الشأن أو ما ياتى بها. يليك الالتزامات المتأهم المعلقة.

ممثل المالك:

الاسم:

الوظيفة:

التوقيع:

التاريخ:

ممثل المقاول:

الاسم:

الوظيفة:

التوقيع:

التاريخ:

نتيجة الطلب:

مستند **A**

مرفوض ويجب إعادة التقديم **C**

مستند مع ملاحظات **B**

مرفوض لا يتم إعادة التقديم **D**

استلام المقاول بالنتيجة

استلام الاستشاري للطلب

التوقيع:

التاريخ:

مجموعة التنمية المتكاملة
Dr. Mohamed Salheen
Integrated Development Group
مشروع
B: Approved As Noted
Date



Plot No. 14 - Al Oula Industrial Park
Developers Area - 6th of October City,
Giza - Egypt.

قطعة ١٤ - مجمع الأولى الصناعي - منطقة
المطورين - مدينة ٦ أكتوبر - الجيزة - مصر

Tel.: (+2) 01119548267 - Fax: (+2) 38588109

Sales: (+2) 01065358936 - (+2) 01022778637

Email: Sales@trichem-eg.com

